



Integration of Distributed Energy Resources: Irish Case


Andrew Keane

University College Dublin

Irish DRES

- Utility Scale
Distributed Resources
- Distributed
Generation < 30 MW








TRANSMISSION SYSTEM 400, 275, 220 and 110 KV JANUARY 2013

- 400kV Lines
 - 275kV Lines
 - 220kV Lines
 - 110kV Lines
 - 220kV Cables
 - 110kV Cables
 - HVDC Cables
 - 400kV Stations
 - 275kV Stations
 - 220kV Stations
 - 110kV Stations
- Transmission Connected Generation**
- Hydro Generation
 - Thermal Generation
 - Pumped Storage Generation
 - Wind Generation






Utility Context

- Active facilitator of renewable energy
- Balancing act of obligations
 - Primarily to demand customers
 - Also now to generation customers
- 2020 RE Target is 40% of electricity to be renewable (~6,000 MW)
- Approximately half of which will be Distributed RES



Ireland Wind Connections (MW)





Policy and Regulatory Challenges

- Financing of projects is challenging for developers due to high upfront capital costs
 - Certainty around revenue improves this situation
 - Drives governments to establish Feed in Tariff mechanisms
- Priority export for renewable energy
- **Intersection between technical and policy requirements and objectives**



Group Processing Approach

- Policies and regulations supporting DER need to (in some way) reflect technical reality of electrical network
- Areas of high density energy resource
- Multiple generators seeking to connect
- Consider network design for cluster as a whole
- Guarantees that wind power available is able to be utilised
- Largely eliminates issues related to variability



Challenges Faced

2003

System Operator placed a moratorium on all wind connections due to concerns over system security

December 2004

Moratorium lifted

January 2005

Group Processing
Approach launched
Gate 1: 373 MW


January 2007


New Round of Connections
processed and offered
Gate 2: 1300 MW

January 2011

New Round of Connections
processed and offered
Gate 3: 4000 MW

Group Processing







Advantages and Disadvantages

- Rapid connection of large volume of renewable generators
- Provision of high quality connections to the grid
- Relatively large upfront capital network investment
 - Cost absorbed by electricity customer and wind farm developers



New Challenges

- Growing public opposition to wind turbines and overhead lines
- Growing public opposition to renewables incentives
 - Macroeconomic environment
- Connection of micro-generation (Solar PV)
 - Deeper into the grid generation is located, fewer existing technology options to integrate it
- Complex technical limitations



Innovation Options

- Real time management of resources
 - Centralised or distributed
- New connection arrangements for DER
 - Potential removal of right to export all power
 - Potential to provide lower cost connections
 - Requires greater ongoing monitoring and management
- Network automation and control



Summary

- Unique technical innovation coupled with appropriate policy and incentives
- High reliability of bulk system has limited drive towards microgrids (so far)
- Coordination of operation between utility operators, developers and regulators on island is central to achievements to date and further progress